


# ATLAS Commissioning

Roberto Ferrari

Montecarlo Workshop

Frascati - 20 Febbraio 2008

# ATLAS Detector



# ATLAS Detector



- 3 sottosistemi principali + sistema magnetico:
  - Sistema magnetico
    - Solenoide centrale
    - Toroidi barrel e endcap
  - Tracciatore Interno:
    - Pixel
    - Silicon Tracker (SCT)
    - Transition Radiation Tracker (TRT)
  - Calorimetria:
    - Calorimetro Elettromagnetico (LAr)
    - Calorimetro Adronico (Tile)
  - Spettrometro per Muoni:
    - Barrel
    - EndCap




# Performance di progetto

<b>MAGNETS</b>	<b>4 magnets: 3 large air-core toroids (to minimize mult.scattering) 1 solenoid (B=2T) in inner cavity</b>
<b>TRACKER</b>	<b>Si pixel + strips TRD (straw tubes with radiator) → particle ID <math>\sigma/p_T \sim 5 \times 10^{-4} p_T \text{ (GeV)} \oplus 0.01</math></b>
<b>EM CALO</b>	<b>Lead/Liquid Argon <math>\sigma/E \sim 10\%/\sqrt{E} + 0.007</math></b>
<b>HAD CALO</b>	<b>Fe-scint. Tiles <math>10 \lambda</math> <math>\sigma/E \sim 50\%/\sqrt{E} \oplus 0.03</math></b>
<b>MUON</b>	<b>Air core toroids, precision and trigger chambers <math>\sigma/p_T \sim 3\% \text{ at } 100 \text{ GeV}, 10\% \text{ at } 1 \text{ TeV}, \text{ stand-alone}</math></b>




# ATLAS superconducting magnets



- Hybrid of 1 Central Solenoid, 1 Barrel and 2 End Cap Toroids
  - 2T magnetic field for inner detector (solenoid) and  $\sim 1$ T for the muon detectors (toroids)
  - 20 m diameter x 25 m long
  - 10000 m<sup>3</sup> field volume
  - 170 t superconductor
  - 700 t cold mass
  - 1320 t magnets
  - 7000 t detector
  - 90 km superconductor
  - 20.5 kA at 4.1 T
  - 1.6 GJ stored energy
  - 4.7 K conduction cooled
  - 9 yrs of construction 98-07



- The largest system of toroids ever built !



□ **ATLAS Magnet System:**  
**Central Solenoid**  
**Barrel Toroid**  
**End-cap Toroids**

# Central Solenoid



**Provides 2T field with a stored energy of 38 MJ for the inner tracker**


**Integrated design within the barrel LAr em calorimeter cryostat**

**Minimize material before EM calorimeter**



- **Inserted into the LAr cryostat in Feb. 2004**
- **Tested at full current (8 kA) in July 2004**

# August 2006: Solenoid fully operational



- **May 2006:**  
→ Cooled at 4 K
- **July – August 2006:**  
→ fully commissioned *in-situ* up to 8.0 kA


Operation current at 7.73 kA for 2.0 T field

## Commissioning studies:

- **3 Fast Dump**  
**T<sub>max</sub> = 100 K**
- **Max. 8.0 kA (with iron)**



# Tracciatore Interno



## Pixel Detector


- 50 x 400  $\mu\text{m}$  pixel
- risoluzione 12 x 100  $\mu\text{m}$
- 80M canali

## Semi-Conductor Tracker (SCT)

- 80  $\mu\text{m}$  pitch
- risoluzione 16 x 580  $\mu\text{m}$
- 6.2M canali

## Transition Radiation Tracker (TRT)

- 4mm  $\emptyset$  straw, lunghe fino a 1.5m
- risoluzione 170  $\mu\text{m}$
- 298k canali




# Integrazione SCT+TRT




barrel integration: february 2006

- endcapC september 2006
- endcapA november 2006



Cosmic data was taken at SR1 for the combined barrel and one of the combined endcaps,

ATLA



Barrel cosmic data set-up in SR1





# SCT/TRT Cosmics Test on Surface

## 2006 combined SCT & TRT barrel cosmic run:

- 22% SCT, 13% TRT barrel
- No B-field
- ~400k events

TRT barrel, Local  $\chi^2$ : the algorithm converges



## SCT & TRT endcap cosmic run:

### Validation of survey data:

- Usage of SCT survey information

improves residuals by 10-20%

# Installazione SCT/TRT



SCT+TRT barrel, august 2006



Barrel had to be fully tested before end-caps could be installed!

SCT+TRT endcap, may 2007

# SCT (EndCap-A) Performance



**Bias Current**  
Measured at 150V  
All modules below  
 $2\mu\text{A}$





**Module Temperature**  
Average Temp =  $25.3 \pm 1.5^\circ\text{C}$   
Uniform across detector  
No hotter areas



# SCT (EndCap-A) Noise

- **Pit Temperature = 25°C**
  - Outers: 1753 e
  - Middles: 1681 e
  - Inners: 1172 e
  - Short Middles: 1009
- **SR1 Temperature = 15°C**
  - Outers: 1675 e
  - Middles: 1609 e
  - Inners: 1121 e
  - Short Middles: 960 e
- Data agree with temperature difference




No Increase in noise when Barrel Operational


# SCT Tracking with Cosmics




~9 million triggers taken in 'physics' mode, including ~450k cosmics triggers



**SCT Hit Efficiency after alignment  
>99%**




# TRT in Milestone Week 5 (1)








# TRT in Milestone Week 5 (2)



Events with L2 tracks




- Efficiency of the L2 tracks with respect to TRTViewer monitoring

Trigger from scintillation counter (2ns jitter) and tile calorimeter




# TRT in Milestone Week 5 (3)

One stack.



All stacks




$\sigma \sim 300 \mu\text{m}$ . Expected  $\sim 220 \mu\text{m}$

Possibly due to threshold/Gas Gain issue (ArC02 gas)


# L1 and L2 Pixel Assembly




Pixel Layer2, half shell




Pixel Layer2, once clamped, outside



Pixel Layer2, once clamped, inside




Pixel Layer1&2, once clamped + services







# Pixel Cosmics Test on Surface




Test of one full Endcap  
~150k cosmic tracks  
Noise occupancy below 1E-8  
< 1% bad channels



Residuals before and after alignment:



# Installazione Pixel



Inserimento nell'ID il 26 giugno 2007

06/28/2007:

Installazione ID completa

Inizio 2008:

ID operativo



Allineamento iniziale con cosmici



# Stato Tracciatore

- Rivelatori completamente installati da giugno 2007
- TRT e SCT cablati e commissionati
- Cablaggio Pixel iniziato il 5 febbraio
  - Termine previsto per inizi aprile
  - Certificazione prevista per fine aprile
  - Catena di lettura DAQ completamente testata (generazione di pattern casuali nella elettronica di lettura)
- Canali morti/rumorosi  $< 1\%$



## ... some concern

- Sorgente principale di preoccupazione (e di ritardo):
  - corrosioni e rotture a connessioni nel circuito di raffreddamento
    - ==> elementi critici (“evaporative heaters”) già sostituiti e spostati in zone meglio accessibili






# Calorimetri a LAr e a Tile

**ECAL:**  
Accordion Pb/LAr  
Barrel:  $|\eta| < 1.475$   
Endcap:  $1.375 < |\eta| < 3.2$

**HCAL:**  
Tile: Fe/Scintillator  
 $|\eta| < 1.7$   
HEC: Cu/LAr  
 $1.5 < |\eta| < 3.2$   
FCAL: Cu/W/LAr  
 $3.1 < |\eta| < 4.9$



# Barrel Calorimeters (LAr + Tiles)



*November 4th 2005: moved to the center of ATLAS*



**All components installed (detectors, cryogenics, services,..)**

ATLAS Commissioning

# End-Caps LAr and Tile Calorimeters



**End-cap Side C** : assembled in the cavern by January 2006

**End-cap Side A** : assembled in May 2006


## Main end-cap LAr activities:

### EC-A:

- Since August 06 installation of FE electronics
- November 2006 start cool down
- February 2007 start cold operation

### EC-C:

- Since April 06 installation of FE electronics,
- February 2007 start cool down
- April 2007 start cold operation



Completed end-cap calorimeter side C, just before insertion

# Lar Status




All cryostats filled and operated continuously for several months

Liquid purity stable and well below 0.5 ppm

Calorimeter Temperature very stable, average within  $\pm 10$  mK.

All back-end electronics available in the readout







# Lar Commissioning

- Pedestal (noise) stability within  $\sim 0.05$  ADC
- Calibration pulse stability  $< 1\%$


- Pedestal variation over 4 months






# LAr Commissioning with Cosmics

- Data taking on week-ends and M. weeks
- Rate: 15 ev/min, Tile triggered
- About 500k events registered since Aug 06
- Optimize timing, intercalibration, uniformity




- Most probable value vs  $\eta$



# Desaster

**Nov: EC Toroid destroys  
cryoline of LAr End-cap C**





**Formation of bellows  
in place on cryoline of LAr  
End-cap C**



**Cryoline of LAr End-cap C  
successfully repaired**

# Tile Hadronic Calorimeter



- **Commissioning with laser:**
  - pulse all PMT at the same time
  - test full readout chain
  - equalize arrival time
  
- **Charge injection:**
  - inter calibrate electronics chain





# Tile Commissioning with Source


- **Hydraulically moved Cs source of ~10 mCi**
- **Dedicated calibration run, with source traversing each one of 463k tiles**
- **Tune HV setting and inter-calibrate response of each readout channel**






# Tile Commissioning with Cosmics



## Uniformity vs eta




- Energy deposition



- Time of flight measurements



## Time resolution




# Some more minor fun ...



- Both for Lar and Tile, several components needed retrofitting/refurbishing:
  - High voltage power supplies
  - Low voltage power supplies (MTBF still an issue for LAr: looking for backup solution)
  - Front end electronic board (work on going)


Refurbishment Progress Chart



Tile Drawers refurbishing



# Spettrometro a muoni




# Toroidal Magnetic Field

Large volume air core system: strong bending power with minimal multiple scattering

Barrel toroid tested at 20.5 kA


End-caps tested at 10 kA (not in final position)



# Barrel Magnet Toroid cooling down



- All magnet services connected and operational (vacuum, power, cryogenic)
  - Vacuum  $< 5 \cdot 10^{-5}$  mbar reached
- Started on 3 July, takes 5 weeks nominally
- Finally cooled down at 4.7K on 30th August






# Barrel Magnet Toroid tests

## ■ Phase I (27 Sep - 14 Oct) : 0-300A

Cleaning: Large platforms removed


- Test of toroid inductance, resistances, fine tuning of coil cooling, identification of quench heaters etc.
- Check of cabling, identification of all sensors



## ■ Phase II (16 Oct - 26 Oct) : 1-5kA

■ Cleaning: Detector area, completely

- Magnet Safety test : 3h test duration at 20kA of the power circuit, toroid not connected
- The 8 BT coils are powered in series on 1 power supply
- Power supply adjustments, slow and fast dumps, quench heater tests, check of coil mechanics
  - *Fast dump tests: first 25 October*
- First readings of mechanical sensors, tie rods, fixed points



# Phase III 5-21 kA

9-10 November 2006:


Up to the nominal current



ATLAS BT MCS

T: BT\_Current\_Leads

Bad 2006/11/10 02:37:11.545 QXZSH\_A\_ALINF07 (CL cooling req ON) AND (Flow QXZSH\_A) ALARM Position Status FALSE S 143/143 33 Unack.



10-Nov-2006 02:37:49.137

<input type="checkbox"/> CL1_PT1000	77.9	K	<input type="checkbox"/> Mass Flow CL1	0.25	g/s
<input type="checkbox"/> CL1_carbon	82.1	K	<input type="checkbox"/> Mass Flow CL2	0.27	g/s
<input type="checkbox"/> CL2_PT1000	78.3	K	<input checked="" type="checkbox"/> Current	0.0	A
<input type="checkbox"/> CL2_carbon	82.4	K	<input type="checkbox"/> Cryogenic carbon	58.4	K






# 18-19 November: 24 h test of Toroid Barrel



Cosmic ray data taking  
with muon sector 13  
- 1M events collected


The first track with  
magnet on triggered  
by the RPCs!!



ning




# ECT-A&C cooling down in parallel




- First cool down of ECT A&C in parallel completed within 5 weeks
- No problems: thermal shield runs at 50-60 K, cold mass at 4.6 K

# 10 kA Slow and Fast Dump



- 0-10-SD and 0-10-FD by quench detector
- $T_{\text{max}}$  cold mass  $\sim 35$  K,  $T_{\text{conductor}} \sim 50$  K
- All coils do not quench simultaneously, delays to be checked at 21kA

# ECT-C: 15 kA and surprise.....



- Toroid behaved fine and past 15 kA!
- At 14.8 kA toroid moved unexpectedly towards TC/ECC and a slow dump was manually triggered, what happened?

# Test configuration and forces




## Configuration

- ECT tested in provisional position to allow repair access to ID
- Much smaller gap to iron in TC
- This position was considered safe, expected friction force  $>68$  t ( $0.2 \times 340t$ )


## Forces at 15 and 21 kA?

- Measured  $\sim 20$  t
- Calculated  $\sim 20$  t at 15kA
- and 40 t at 21kA , so  $\ll 70$  t safe!
- **Still not understood why it moved**

Tests  $>10kA$  postponed to final configuration in May 08



Final configuration




Test configuration



# Muon Chambers

The high momentum resolution is achieved with 3 layers of high precision tracking chambers arranged in 3 cylindrical layers (barrel) or perpendicular to the beam (end cap wheels).

Trigger chambers make part of the LVL1 trigger in ATLAS providing BC identification, muon  $p_T$  triggers selection and second coordinate information



	Function	Resolution (RMS) in			Chambers	Chan nels	Coverage
		$z/R$	$\phi$	time			
MDT	Tracking	35 $\mu\text{m}$ (z)	-		1108	339k	$ \eta  < 2.7$
CSC	Tracking	40 $\mu\text{m}$ (R)	5 mm	7 ns	32	31K	$2.0 <  \eta  < 2.7$
RPC	Trigger	10 mm (z)	10 mm	1.5 ns	544	359k	$ \eta  < 1.05$
TGC	Trigger	2-6 mm (R)	3-7 mm	4 ns	3588	318k	$1.05 <  \eta  < 2.7$ (2.4 for trigger)



# MDT Installation

Barrel: 701/704 stations installed, 96% precisely positioned;  
commissioning on-going

End-caps: installation of small wheels on-going

## Small Wheels

JD: Shielding and support disk ~10 m diameter

CSC large and small chambers on each side of the wheel

MDT large and small chambers on each side of the wheel

TGC






# Small Wheels Test


**All detectors working correctly at nominal voltage**

**Dead channels: CSC&TGC  $\rightarrow$  0.06% MDT  $\rightarrow$  0.03%**

**CSC noise**



**MDT tube occupancy**



**GAS: none has gas leaks**

**TGC  $< 0.1$  mb in 5 min at twice the working pressure**





ATLAS Commissioning




ATLAS Commissioning

# Barrel Commissioning: Sectors



- MDT:
  - Sectors from 3 to 8 Commissioned with Cosmic rays
  - Sectors 1-2 & 9-10 noise test (missing HV-PS's)
  - Sectors 11-12 under test
  - Many problems found and solved



## ▲ *List of remaining problems*

- ▲ *% Dead tubes less than 1‰*
- ▲ *Some noisy wires mainly on BOS*
- ▲ *# HV trips: 2*
- ▲ *# Gas leaks: 18 yet unfixed leaks*

Mean Occupancy < 0.1%

# MDT DCS



- DCS: All systems in advanced state, but not all yet integrated in Central DCS.

HV/LV + monitoring of FE electronics T and V


Alignment

B-field

T-sensors

Gas

Initialization




# Barrel/EC Commissioning: Calibration Stream



- ▶ The Muon Calibration Data Stream provides large samples of muon data extracted before LVL2 decision (Only data in Region Of Interest).

## MDT Residuals after calibration


- During Milestone Week 4:
  - Calibration Stream emulated offline, data sent (offline) to Tier2
- ▶ During Dec. muon run:
  - ▶ Calibration stream extracted online from LVL2




# Barrel Commissioning: RPC sector commissioning




- Sectors 3-6 commissioned up to Cosmic rays:
  - Dead strips= 0.2%
  - Disconnected gaps for HV problems 0.6%
  - Disconnected gaps for Gas Leak 0.2%
  - Noisy channels: few units
  - Average Noise 0.4 Hz/cm<sup>2</sup>
  - LVL1 Timing-In
- ▲ Sector 7 & 8 under Cosmic ray test now



# EC commissioning: TGC results



- Both trigger & read-out paths working
  - Fibre length measured for each sector






✦ Trigger Latency measured:  
86-90 clk

✦ Most data recorded in the  
Current Bunch Crossing: Trigger  
timed-in



# Commissioning with Cosmics

- Trigger by top RPC sectors
  - rate  $\sim 200$  Hz
- Cosmics rays acquired on
  - 10/16 MDT sectors
  - 4-6/16 RPC sectors
- Bad/Dead channels  $< 0.5\%$







# ... sofferenze

- ✦ *General common issue: availability of (CAEN) power supplies*
- MDT Barrel and EC:
  - ✦ EOL chambers commissioning
- RPC & Muon Level 1 Trigger
  - ✦ Commissioning speed
  - ✦ Gas leaks
  - ✦ Gas system commissioning
- ✦ TGC
  - Access problems
  - Gas system commissioning



# TDAQ Commissioning



- Level-1 Trigger
- HLT infrastructure
- DAQ infrastructure
- DAQ software
- Commissioning (Technical)  
Runs




# Trigger/DAQ architecture

**Level-1 Trigger**  
Custom Pipelined Hardware

**Region of Interest Builder**  
Custom Hardware

**High-Level Trigger**  
Large PC farm  
High data bandwidth  
Dedicated 'Data' Network



Detector Front End Electronics (Detector responsibility)  
Detector RODs


Readout System  
Custom built buffers in ROS PC farm

Event Building  
More PC farms on 'data' network

DAQ software - control, configuration, monitoring (control network)

# Level-1 Trigger System


- Three major systems
  - Calorimeter Trigger
  - Muon Trigger
  - Central Trigger Processor (CTP)
- Other triggers and signals also integrated by CTP
  - Minimum bias
  - Luminosity triggers
  - Beam Pick-up
- CTP distributes all timing information, (available since 2006, now fully installed)



# Level-1 Muon/Calorimeter Trigger



- Calorimeter trigger installation completed in December 2007
- Muon trigger essentially complete
  - on-detector electronics power supply and gas issues
  - commissioning done sector-by-sector




ATLAS Commissioning





# Level-1 Trigger Commissioning

- Calorimeter trigger signals need thorough testing before access disappears
  - About half tested so far
- Muon trigger commissioning sector by sector



- Timing needs to be addressed





# Technical Runs

- Inject Montecarlo event fragments in the readout buffer
- Send level-1 trigger information to the system
- Data acquisition and monitoring ~ as in real time
- Software validation
- Hardware commissioning
- Configuration issue
- Debugging
- Scaling issue

# Technical Run Display



The screenshot displays a complex technical interface with several overlapping windows:

- ATLAS Logbook:** Shows the ATLAS experiment logbook with a table of entries. The table has columns for ID, Date, valid, Author, Type, System, Status, and System Affect.
- Network Browser:** Displays a network tree on the left and a traffic graph titled "sw-data-core-dc-01\_235208767 Total TRAFFIC (Load)". The graph shows utilization (%) over time from 14:00 to 12:00. A legend indicates Input Load (red) and Output Load (blue). Summary statistics are provided: Input Load (222.43 u, 5.73 Avg, 12.19 Max), Output Load (123.63 u, 125.54 m, 592.45 m).
- ATLAS TDAQ Software GUI:** Shows the "RUN CONTROL STATE" as "RUNNING" in a green box. It includes buttons for Shutdown, Boot, Unconfig, Config, Stop, Start, Pause, and Continue. Run information includes Run type (Physics), Run number (37573), Run Start Time (09/02/08 10:57:07), and Total run time (01:33:05). A table lists event filter levels with their respective rates.
- nagiosgraph:** Shows a "Daily" memory usage graph for "pc-tdq-xpu-0008-MEM". The graph shows memory usage (used) over time from Friday 12:00 to Saturday 12:00. Summary statistics: Max: 73.00, Avg: 59.02, Min: 21.00, Cur: 64.00.

1.5 hour  
running time

stable  
trigger rate

memory  
leak spotted







# ATLAS Integration

- Combined mode running:
  - Milestone #N Weeks every 6-8 Weeks
  - M5 in November 07, M6 scheduled for March 08
- Goal:
  - Software and hardware integration
  - Cosmic data taking
  - Monitoring
  - Timing


# M5 combined run




- RPC (12.5%): Sectors 5,6
- MDT (~25%): barrel sectors 3-6, 16EIL4 chambers
- TGC: 5/36 stations with final setup in read out and trigger on each side (~14%). First operation on A-side
- Tile: ~55%; LAr: 68%-87%
- Pixel: Readout only, no TRT (but M4 and M5.x in Dec)



- ✓ Cosmic trigger:
  - Tile: sub-Hz
  - RPC: few tens Hz
  - TGC: few Hz
  - L1Calo: sub-Hz
  - MBTS: sub-Hz





- ✓ Technical triggers:
  - random, fixed frequency from CTP






# M5 Achievements




- End-cap MDT show hits for both RPC and TGC trigger
- Different T0 is as expected








# LAr and Tile cosmics



## Correlation TileTime vs LArTime



## Correlation | Tile( $\phi, \eta$ ) and LAr( $\phi, \eta$ )






***Since some time now the ATLAS Control Room is a major centre of actions***

***This has of course increasingly been so, and the ACR soon will be staffed permanently when full-time shift presence starts***



# Non e' finita:

- **Full Dress Rehearsal:** realtime tests of hardware, software, databases, storage media, networks, data flow, data integrity and quality checks, calibrations, etc



“FDR-1 run was a difficult success—data were played through and are now at Tier1 and Tier2 sites:

Finding problems was the goal; most were overcome

For FDR-2 expect basics to run more smoothly”



# Prossimo futuro ...

## Schedule linked to beam pipe closure (T0)

Detector: ~ 5-6 weeks before T0 start closure to final position: close ID, move back calorimeters (-3m), install Small Wheels, position ECT, test magnet system, shielding

### Operation:

- Keep current mode global commissioning along two lines up to T0-2 months
  - Periodic (~ 2 months) global commissioning (Mx) weeks for integration, operation, training, cosmic runs
  - System dedicated periods (few days/system) for addressing specific issues
- Move to continuous mode starting at T0-2 months

# Commissioning Feb/Mar 08




Month	Date	System	Requirements, remarks	CS	Parallel
February	4-8	DAQ/HLT	Technical Run	yes	FDR, SCT
	9-10				TRT, SCT
	11-13	Tile	Calibration Triggers	yes	SCT; TRT; 13/2 11:00 DAQ/HLT 24h
	14-15	Tile	R/O debugging	Yes	TRT; TDAQ 24h up to 14/1 at 11:00
	16-17				TRT
	18-20	TRT+SCT	Scintillator trigger	Yes	
	21-24	L1Calo, Tile, LAR	Calorimetry days Lar may join if possible	Yes	TDAQ 24h period 20-2. TBC wrt ID progress
	25/2-2/3	Muons+TRT	TRT "comes in" when ready "at times"	Yes	TDAQ 24h period 27-28 Dedicated to HLT
March			RPC pointing trigger needed by TRT (wish)		
	3-10	M6			





# ... T0



## Move to continuous mode

- [T0 -2 to T0 -1] Assessment month: Check system stability, controls, Data Quality/monitoring.
- [T0 -1 to T0] Semi-continuous Global Cosmic Run (GCR) and problematic detector out for debug.
- [T0 to T0 + 1] Global Cosmic Run; start 24/7
- [T0 + 1 to T0 + 3] ATLAS Run: commissioning with beams, global run with beam/cosmics, timing, 24/7 operation



# Conclusioni

Molte attività in parallelo per commissioning di rivelatori, sistemi di controllo, trigger, data acquisition, monitoring, ricostruzione

Sottorivelatori vicini alla fine delle attività di commissioning individuale

Milestone Week Mx fondamentali per la transizione all' "ATLAS mode"

Raggi cosmici forniscono il modo migliore di calibrare il rivelatore e il sistema di trigger